

Items	Description	Qty	Unit
I.	<u>PRELIMINARIES</u>		
1.01	Construction Bond (by OWNERS ACCOUNT)	N.I	N.I
1.02	Water consumption (by OWNERS ACCOUNT)	N.I	N.I
1.03	Electricity consumption (by OWNERS ACCOUNT)	N.I	N.I
1.04	Permits - Building Permit/Occupancy	1.00	lot
1.05	Insurance / CARI	1.00	lot
1.06	Mobilization/Demobilization	1.00	lot
1.07	Lay-out and chalk line	1.00	lot
1.08	Temporary Power connection	1.00	lot
1.09	PPE's and Fire protection during construction	1.00	lot
	OTHERS		
1.11	As-Built Plans of combined services Drawings, Manuals and Maintenance Documents	1.00	lot
1.12	General Cleaning	1.00	lot
1.13	Hauling of Debris	1.00	lot
1.14	Supervision	1.00	lot
1.15	Logistics	1.00	lot
1.16	Scaffolding	1.00	lot
	TOTAL-PRELIMINARIES		
II.	<u>BUILDER'S WORK</u>		
	Supply and execute the following items as required according to drawing, layout & Intent		
2.01	Secondary wall to be attached to permanent wall		
	Supply and Installation of 150mm Secondary Walls using 4" CHB @ 3.2m HT. including stiffener/lintel/zocalo/Plastering	48.70	sq.m

Items	Description	Qty	Unit
	Supply and Installation of 12mm Gypsum Board @ 3.2m HT in metal furring. Loc.: Dining and Display Area	98.14	sq.m
2.02	Internal Partition		
	Supply and Installation of 4" CHB @ 3.2m HT. including stiffener/lintel/zocalo. Loc.: Kitchen, Office and Common Restroom	49.18	sq.m
	Supply and Installation of 12mm Gypsum Board in Metal Framing @ 3.2m HT. Double Face Loc.: Storage Area	13.31	sq.m
	Supply and Installation of Low Concrete Wall @ 1.0m HT for Bar Counter including stiffener/lintel/zocalo Loc. Matcha Bar	8.10	sq.m
	Supply and Installation of 12mm Gypsum Board in Metal Framing @ 2.4m HT. Single Face Loc.: Cove Wall @ Common Restroom	5.28	sq.m
2.04	Waterproofing Works using Hot applied PU. Loc.: Kitchen, Common Restroom and Bar	33.39	sq.m
2.05	Waterproofing Works using Cold applied powermix - 4 coats. Loc: Dining	59.68	sq.m
2.05	Consumables	1.00	lot
	TOTAL-BUILDERS WORKS		
III.	<u>FLOOR FINISHES</u>		
	Prepare and Install the following floor finishes including required cement screed, mortar, grouts adhesives and accessories as required per area		
3.01	Floor A: Supply and Installation of ST-03 1200mm x 600mm Granite Tile TD*5149BM Pearl Blue Natural Finish by South East Gate Phils. Loc.: Dining Area . Alternative: Tile Express	77.05	sq.m
3.02	Floor B: Supply and Installation of ST-01 200mm x 200mm Pietra Occitana Beige in Anti-Slip/Textured Finish by Taps N Tiles. Loc.: Kitchen Alternative: PIETRA OCCITANA BIANCO ANTI SLIP 20X20cm by Taps N Tiles (Original specs is out of stock as per supplier) . Alternative: Tile Express	12.68	sq.m
3.03	Floor C: Supply and Install of 600mm x 1200mm Ceramic Tile. Loc: Common Restroom	3.50	sq.m

Items	Description	Qty	Unit
3.03	Floor D: Supply and Install of 600mm x 600mm Ceramic Tile. Loc: Storage and Office Area	3.75	sq.m
3.04	Supply and Install of 3mm Metal Floor Strip. Loc: Entrance, Storage, Restroom and Office	7.54	lm
3.05	Consumables	1.00	lot
	TOTAL-FLOOR FINISHES		
IV.	<u>WALL FINISHES</u>		
	Supply and Install the following items including all substrates, accessories and preparations as required		
4.03	Supply and installation of ST-02 600mm x 600mm Verona Tundra White Matte by Taps N Tiles. Loc: Kitchen Alternative: MODERN IVORY NATURALE 60x60cm by Taps N Tiles (Original specs is not from Taps N Tiles). Alternative Tile Center	41.04	sq.m
	Finish for Toilet	15.95	sq.m
4.08	Consumables	1.00	lot
	TOTAL-WALL FINISHES		
V.	<u>CEILING WORKS</u>		
	Supply and Install the following items including all accessories as required		
5.01	Supply and Installation of 20mm thk. Gypsum Board in Metal Furring. Loc.: Ceiling A, Ceiling B, Ceiling E & Ceiling F	105.54	sq.m
5.03	Supply and Installation of 3/4" thk. Marine Plywood in Metal Furring including cove ceiling. Loc.: Accent Ceiling	10.80	sq.m
5.04	Consumables	1.00	lot
	TOTAL-CEILING WORKS		
VI.	<u>CEILING FINISHES</u>		
	Supply and Install the following items including all accessories as required		

Items	Description	Qty	Unit
6.02	Ceiling D - Supply and Installation of 600mm x 600mm Kalamansi Skin Ceiling Board. Loc.: Kitchen	12.71	sq.m
6.03	Supply and Installation of WD-02 1200mm x 2400mm x 3.5mm thk. Black Diamond Veneer EV Ebony Black. Loc.: Ceiling accent	6.70	sq.m
6.04	Consumables	1.00	lot
	TOTAL-CEILING FINISHES		
VII.	<u>PAINTING WORKS</u>		
	Supply and Apply 3 coats Paint the following including required area preparations, consumables and accessories		
7.01	CEILING		
	P-02: Dunn Edwards DEC719 Coral Clay in Eggshell Finish; Loc.: Ceiling A . Alternative:Boysen	28.84	sq.m
	P-01: STUCCO #3 C-1.5P L15P DET676 MUSCAL BLANC in Rough Finish by Pieni Loc.: Ceiling B - alternative: Lancaster	51.06	sq.m
	Paint for 60x60cm Kalamansi Ceiling Board Loc. Ceiling D	12.71	sq.m
	Ceiling E - Paint Finish Loc. Storage Area	3.51	sq.m
	Ceiling F - Paint Finish Loc.: Office Area	3.73	sq.m
7.02	WALLS		
	P-01: STUCCO #3 C-1.5P L15P DET676 MUSCAL BLANC in Rough Finish by Pieni; Loc.: General Wall/ Millworks/Banquette- alternative: Lancaster	103.43	sq.m
	P-02: Dunn Edwards DEC719 Coral Clay in Eggshell Finish; Loc.: Beverage Counter . Alternative:Boysen	26.26	sq.m
	Painting Works for Storage Area and Office Area	51.38	sq.m
7.03	Consumables	1.00	lot
	TOTAL-PAINTING WORKS		
VIII.	<u>DOORS & HARDWARES</u>		

Items	Description	Qty	Unit
	Supply and Install the following items including all frames, subframes, glazing, hardware and accessories as required		
8.01	D-01: 1000mm x 2100mm Single Swing Concealed Wooden Door in P-02 Paint Finish. Loc: Kitchen	1.00	set/s
8.02	D-02: 2600mm x 4300mm Polycarbonate Accordion Door. Loc.: Entrance	1.00	set/s
8.03	D-03: 700mm x 2100mm Single Swing Wooden Door in Paint Finish. Loc: Office and Storage Area	2.00	set/s
8.04	D-04: 1150mm x 2100mm Wooden Sliding Door in Pain Finish. Loc: Common Toilet	1.00	set/s
8.05	Consumables	1.00	lot
	TOTAL-DOORS & HARDWARES		
<u>IX.</u>	<u>GLASS & GLAZING</u>		
	Supply and Install the following items including all frames, subframes, glazing, hardware and accessories as required		
9.01	Supply and Installation of Laminated Glass in Beige Kote Kumiko Pattern by Kraut Art Glass in 1" x 1" Metal Tubular Frames in paint to match P-02 Alternative: 8mm thk. clear glass with sticker to match Beige Kote Kumiko Pattern	1.00	set/s
9.02	Supply and Installation of 6mm thk. Mirror with Frame in Irregular Shape - 2 sets	1.00	lot
9.03	Consumables	1.00	lot
	TOTAL-GLASS & GLAZING		
<u>X.</u>	<u>MILLWORKS</u>		
	Supply and execute the following items as required according to drawing, layout & Intent, including all necessary hardwares, accessories and consumables		
10.01	Banquette Seat - supply and installation of wood carcass using 3/4" marine plywood in P-01 Stucco Finish-See painting works	1.00	set/s

Items	Description	Qty	Unit
10.02	Matcha Bar Counter - supply and installation of wood carcass using 3/4" marine plywood in WD-01 solid wood finish- Front Counter	1.00	set/s
10.04	Bar Back Counter - supply and installation of wood carcass using 3/4" marine plywood in WD-01 solid wood finish- Base Cabinet	1.00	set/s
10.05	Bar Overhead Cabinet - supply and installation of wood carcass using 3/4" marine plywood in P-01 Stucco Finish-See painting works	1.00	set/s
10.06	Floating Shelves - supply and installation of wood carcass using 3/4" marine plywood in P-01 Stucco Finish-See painting works	1.00	set/s
10.07	Round Table 1 - 500mm dia x 730mm round table using 20mm thk tabletop in Solid Wood Stained finish (to match WD-01) with 6mm thk. SS table legs and base	7.00	set/s
10.08	Round Table 2 - 800mm dia x 900mm round table using 10mm thk tabletop in SS finish with 6mm thk. SS table legs and base	1.00	set/s
10.09	Cylinder Chairs - 390mm dia x 475mm Seat upholstered in standard fabric finish with plywood substrate and solid wood framing. Seat base in painted finish	8.00	set/s
10.10	Stand Up Counter - 1800mm dia. x 1200mm round table using 3/4" marine plywood in Wood Stained finish (to match WD-01) with concrete support in ST-04 finish	1.00	set/s
10.11	Consumables	1.00	lot
	TOTAL-MILLWORKS		
	TOTAL-ARCHITECTURAL WORKS		