

Items	Description	Qty	Unit
I.	<u>PRELIMINARIES</u>		
1.01	Mobilization / Demobilization	1.00	lot
1.02	PPE's and Fire protection during construction	1.00	lot
1.03	Scaffolding	1.00	lot
1.04	Supervision	1.00	lot
1.05	Logistics	1.00	lot
1.06	General Cleaning and Hauling	1.00	lot
1.07	CARI (Contractors All Risk Insurance)	1.00	lot
1.08	Permits - Building Permit / Occupancy Permit/Business Permit	1.00	lot
	Construction Bond-Refundable (by OWNER)	N.I	N.I
	Water consumption (by OWNER)	N.I	N.I
	Electricity consumption (by OWNER)	N.I	N.I
	Carried to Summary-PRELIMINARIES		
II.	<u>BUILDER'S WORK</u>		
	Supply and execute the following items as required according to drawing, layout & Intent		
2.01	Secondary wall to be attached to permanent wall		
	Supply & installation of 150mm thk. Using 4" CHB including stiffener/intel beam/zocalo @ 1.93m HT. Loc.: Kitchen/Staff Locker Room/ Men & PWD Restroom/Dining Area 1 & 2	75.02	sqm
	Supply & installation of 150mm thk. Using 3/4" Marine Plywood in Light Steel Framing @ 4.0m HT. Single Face. Loc.: Café/Dining Area 2	49.68	sqm
	Supply & installation of 150mm thk. Using 6mm Ficem Board in Light Steel Framing @ 2.07m HT. Single Face. Loc.: Kitchen/Staff Locker Room/ Men & PWD Restroom	49.91	sqm
	Supply & installation of 150mm thk. Using 12mm Gypsum Board in Light Steel Framing @ 2.07m HT.Single Face. Loc.: Dining Area 1 & 2	30.55	sqm

2.02	Interior Partition Wall		
	Supply & installation of 150mm thk. Using 4" CHB including stiffener/lintel beam/zocalo. Loc.: Kitchen/Storage/Mop Sink/Dining Area 1 & 2/Reception	38.93	sqm
	Supply & installation of 150mm thk. Using 12mm Gypsum Board in Light Steel Framing. Double Face. Loc.: Kitchen/Storage/Mop Sink/Dining Area 1 & 2/Reception	62.51	sqm
	Supply & installation of 150mm thk. Using 6mm Ficem Board in Light Steel Framing. Double Face. Loc.: Men & PWD Restroom	27.96	sqm
	Supply & installation of 150mm thk. Using 3/4" Marine Plywood in Light Steel Framing. Double Face. Loc.: Café/Dining Area 2	41.36	sqm
2.03	Plastering - 20mm thk.	152.88	sqm
2.04	Floor screed Topping,ready to received Finish Floor	282.78	sqm
	Others		
2.05	Waterproofing Works using P.U Cold applied Process including 300mm coving ht. Loc.: Kitchen/Café/Men's & PWD Restroom/Mop Sink	98.82	sqm
2.06	Consumables	1.00	lot
	Carried to Summary-BUILDERS WORKS		
III.	<u>FLOOR FINISHES</u>		
	Prepare and Install the following floor finishes including required cement screed, mortar, grouts adhesives and accessories as required		
3.01	Supply and Install of Crazy Cut Matte Tiles Loc.: Kitchen/Staff Locker Room/ Men & PWD Restroom/Dining Area 1 & 2/Café	282.78	sqm
3.02	Consumables	1.00	lot
	Carried to Summary-FLOOR FINISHES		
IV.	<u>WALL FINISHES</u>		
	Supply and Install the following items including all substrates, accessories and preparations as required		
4.01	Supply and Install of 300mm x 300mm Green KitKat Tiles. Loc.: Dining Area 2/PDR/Dining Area1/Café	77.58	sqm
4.02	Supply and Install of Black KitKat Tiles. Loc.: Dining Area 2/PDR/Dining Area1/Café	10.13	sqm

4.03	Supply and Install of Wood Veneer. Loc.: Dining Area 2/Dining Area1/Café	59.80	sqm
4.04	Supply and Install of Wallpaper. Loc.: Dining Area 2/Dining Area1	22.89	lm
4.05	Supply and Install of Stainless Steel Panel in Hairline Finish. Loc.: Kitchen	56.88	sqm
4.06	Consumables	1.00	lot
	Carried to Summary-WALL FINISHES		
	<u>CEILING WORKS</u>		
<u>V.</u>	Supply and install the following items including all accessories as required-Note: See Final Paints in Painting Works		
5.01	Supply and Installation of 12mm thk. Gypsum bd. Ceiling including hangers and accessories - for Red Plaster Finish (see painting works)	67.70	sqm
5.02	Supply and Installation of 3/4" thk.marine plywood ceiling for mirror substrate and Moulding including hangers and accessories - (see ceiling finishes)	273.47	sqm
5.03	Consumables	1.00	lot
	Carried to Summary-CEILING WORKS		
<u>VI.</u>	<u>CEILING FINISHES</u>		
6.01	Supply and Installation of 4' x 8' Wood Panel. Loc.: Dining Area 1 & 2/Kitchen/PDR/Café/Men's & PWD Restroom/Storage/Staff Locker Room	214.76	sq.m.
6.02	Supply and Installation of Ripple Metal Sheet. Loc.: Dining Area 1 & 2/Kitchen/PDR/Café/Men's & PWD Restroom/Storage/Staff Locker Room	58.71	sq.m.
6.03	Consumables	1.00	lot
	Carried to Summary-CEILING FINISHES		
<u>VII.</u>	<u>MILLWORKS</u>		
	DD-1: Reception Counter - 1500mm x 600mm x 850mm	1.00	set/s
	DD-2: Retail Counter - 3700mm x 600mm x 850mm	1.00	set/s
	DD-3: Bakery Counter - 3000mm x 750mm x 850mm	1.00	set/s
	DD-4: POS Counter - 3780mm x 750mm x 850mm	1.00	set/s
	DD-5: Back Counter w/ Overhead Shelves - 4500mm x 750mm x 850mm	1.00	set/s

	DD-6: Bakery Back Counter w/ Overhead Shelves - 2900mm x 600mm x 850mm	1.00	set/s
	DD-7: Open Kitchen Counter w/ Hanging Shelves - 4100mm x 700mm x 850mm	1.00	set/s
	DD-8: Open Kitchen Back Counter - 4100mm x 600mm x 850mm	1.00	set/s
	DD-9: Plantbox 1 - 2700mm x 300mm x 950mm	1.00	set/s
	DD-10: Plantbox 2 - 4500mm x 300mm x 950mm	1.00	set/s
	W-2: Fixed Wooden Louver Panel - 3850mm x 800mm	2.00	set/s
	20 x 50mm Wood Moulding - paint to match with Wood Veneer	44.37	lm
	40 x 70mm Wood Moulding - paint to match with Wood Veneer	44.37	lm
	10 x 50mm Wood Moulding - paint to match with Wood Veneer	34.20	lm
	116 mm dia. Decorative Wood Post (half circle) - paint to match Wood Veneer	34.86	lm
	50mm Baseboard	25.42	lm
	Consumables	1.00	lot
6.03	Loose Furnitures/Awning Canopy/Signages-by OWNER	1.00	lot
	Carried to Summary-MILLWORKS		
VIII.	<u>GLASS & GLAZING WORKS</u>		
8.01	D-1: 2000x2400mm Double Leaf Frameless Glass Door w/ Glass Transom and Fixed Panel	1.00	set/s
8.02	W-1: 2000x2650mm Fixed Storefront Glass Panel	7.00	set/s
8.03	Consumables	1.00	lot
	Carried to Summary-GLASS & GLAZING WORKS		
IX.	<u>METAL WORKS</u>		
9.01	Supply and Installation of 150mm S/S Metal Cladding in Hairline Fin. for Pass Thru Window at Kitchen - 550mm x 2500mm	1.00	lot
9.02	Supply and Installation of 150mm S/S Metal Cladding in Hairline Fin. for Pass Thru Window at Kitchen - 550mm x 600mm	1.00	lot
9.03	Consumables	1.00	lot
	Carried to Summary-METAL WORKS		
X.	<u>DOORS & HARDWARES</u>		

	Install the following items including all frames, subframes, hardware and accessories as required		
10.01	D-1: 2000x2400mm Double Leaf Frameless Glass Door w/ Glass Transom and Fixed Panel (see glass and glazing)	Incl.	Incl.
10.02	D-2: 2050mm x 3850mm Double Leaf Wooden Louver Door with Fixed Wooden Transom and Jamb	1.00	set/s
10.03	D-3: 3750x3850mm Four-Leaf Metal Sliding Pocket Door with 10mm thk. Tempered Glass Panel and Fixed Transom	1.00	set/s
10.04	D-4: 4620x3850mm Five-Leaf Metal Sliding Pocket Door with 10mm thk. Tempered Glass Panel and Fixed Transom	1.00	set/s
10.05	D-5: 1000x2450mm Single Leaf Wooden Door with 4 pcs. Round View Panel	2.00	set/s
10.06	D-6: 800x2100mm Wooden Accordion Door	2.00	set/s
10.07	D-7: 850x2400mm Single Leaf Wooden Door	2.00	set/s
10.08	D-8: 1000x2400mm Single Leaf Wooden Door	1.00	set/s
10.10	Consumables	1.00	lot
	Carried to Summary-DOORS & HARDWARES		
XI.	<u>PAINTING WORKS</u>		
	Supply and Apply 3 coats Paint the following including required area preparations, consumables and accessories		
	<u>CEILING</u>		
11.01	Supply and Install of Red Paster Finish - Ceiling Accent Dining Area 2	67.70	sq.m.
	<u>WALL/S</u>		
11.02	Supply and Install of Pink Plaster Finish - General Wall	309.91	sq.m.
11.03	Supply and Install BOYSEN Flat White Latex - Kitchen	15.54	sq.m.
11.04	Consumables	1.00	lot
	Carried to Summary-PAINTING WORKS		